

PLD-E/E5/7966/2021


Date:12/07/2024

Reference: Re-Quotation Notice No. PLD-E/E5/7966/2021 dated :29/06/2024

Re-quotation for "Maintenance works at Ladies Hostel, Nileswaram Campus of Kannur University" -Last date of receiving of Quotation -extended -reg.

The Last date for receiving of re-quotation " Maintenance works at Ladies Hostel, Nileswaram Campus of Kannur University " is extended till 26.07.2024 at 3 PM .Time of opening -3.30 PM


REGISTRAR



KANNUR UNIVERSITY						
QUOTATION SCHEDULE <i>Last date of Receipt: 26.07.24, 3 PM</i>						
Name Of Work: MAINTENANCE WORK OF LADIES HOSTEL AT NILESWARAM CAMPUS						
SL. NO	QTY	PARTICULARS	UNIT	RATE INCLUDING ALL TAXES		AMOUNT (RS)
				IN FIGURES (RS)	IN WORDS (RS)	
1	30	15.23.1 Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	Sqm			
2	30	11.41.2 Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4(1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600 x 600 mm.	Sqm			
3	1	17.69.2 Providing and fixing PTMT Waste Coupling for wash basin and sink, of approved quality and colour. Waste coupling 38 mm dia of 83 mm length and 77 mm breadth, weighing not less than 60 gms	nos			
4	3	50.18.9.7.1 Providing and fixing PVC pipes including of pipes with one step PVC solvent cement, trenching refilling & testing of joints complete as per direction of Engineer in Charge. 63 mm dia 6Kgf/cm ²	metre			
5	3	50.18.9.17.1 Providing and fixing PVC pipes including fixing the pipe with clamps/ clip at 1.00 m spacing . This includes jointing of pipes with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 63 mm dia 6 Kgf/cm ² - External work - Exposed on wall	metre			
6	2	50.18.9.20.1 Providing and fixing PVC moulded fittings/ accessories for Rigid PVC pipes, including jointing with PVC solvent cement - 63 mm dia Elbow	nos			
7	2	50.18.9.20.9 Providing and fixing PVC moulded fitting / accessories for Rigid PVC pipes, including jointing with PVC solvent cement-63 mm dia Socket /coupling	nos			
8	5	50.18.9.14.1 Providing and fixing PVC pipes, fittings including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step PVC solvent cement and testing of joints complete as per direction of Engineer-in-Charge 32 mm dia 10 Kgf/cm ² - External work- Exposed on wall	metre			
9	1	Disposal work of wastes in waste bin	unit			
TOTAL						
(Rupees.....Only)						
Signature:						
Name & Adress of the Quotationer:						
Date:						