

PLD/E3/9430/2026

Date: 22.10.2026

Reference: Retender Notice No.PLD/E3/9430/2026 dated 16.10.2026

Retender for " **Replacing Damaged Roofing Sheets at Terrace Level and Maintanance of Lift Shaft at Library Building, Thavakkara Campus,Kannur University**" -Last date of receiving of Retender -extended -reg. The Last date for receiving of tender " **Replacing Damaged Roofing Sheets at Terrace Level and Maintanance of Lift Shaft at Library Building, Thavakkara Campus,Kannur University**" is extended till 29.10.2026 at 3 PM .Time of opening -3.30 PM

sd/-
REGISTRAR



KANNUR UNIVERSITY
(PLANNING AND DEVELOPMENT BRANCH)
NOTICE INVITING RETENDERS

PLD/E3/9430/2026

16.10.2026

Sealed competitive tenders superscribed as " **Replacing Damaged Roofing Sheets at Terrace Level and Maintanance of Lift Shaft at Library Building, Thavakkara Campus,Kannur University**" are invited from registered competent Contractors/firms.

Sl.No	Name of Work	EMD	Tender Fee	Time for the completion of work	Last date of submission
1	2	3	4	5	6
1	Replacing Damaged Roofing Sheets at Terrace Level and Maintanance of Lift Shaft at Library Building, Thavakkara Campus,Kannur University	Rs.3,725/-	Rs.590/- including GST @ 18%	3 months	22-10-2026 at 3.00 PM

1. Tender Form can be had from Kannur University Website www.kannuruniversity.ac.in.
2. A sum of Rs.590 (including GST @18%) towards the cost of Tender form and an amount of Rs3,725/- as EMD should be remitted **separately** by way of Demand Draft drawn in favour of Finance Officer, Kannur University, payable at SBI South Bazar Branch, Kannur or Kannur Branch of any other Nationalized or scheduled Bank.
3. The Tenderer shall have valid GST registration and shall furnish a copy of registration certificate along with the tender documents.
4. The successful Tenderer before signing the Agreement and within the period specified in the work order, shall deposit a sum equivalent to 5% of the value of the contract as Security Deposit.
5. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges and other charges if any should be furnished separately and nothing extra shall be admissible over and above the rate quoted.
6. The Contractor before submitting Tender for the work shall ensure that, they have visited the Site and satisfied himself about the site conditions for the work (including arranging facilities of water and electricity) and for logistics and smooth flow of workmen ,and materials as well as permission from Authorities for this purpose
7. Payment will be made through account and no advance payment will be sanctioned



8. Defect Liability for the work shall be 1 year from the date of satisfactory completion of the work.
9. Received tenders will be opened on ~~22.10.2024~~ at ~~3.30 PM~~
10. Details of work can be had from the Planning and Development Branch on all working days up to 5 pm.

The Registrar, Kannur University, reserves the right to reject any of the tenders or all the tenders without assigning any reason whatsoever.



To

1. Notice Board
2. Website

Sunil Kumar S

REGISTRAR (i/c)

KANNUR UNIVERSITY
CIVIL STATION. P. O.
KANNUR - 670 002



KANNUR UNIVERSITY						
TENDER SCHEDULE						
Name of the work: -Replacing damaged roofing sheets at Terrace level and Maintenance of lift shaft at Library building,Thavakkara campus,Kannur University						
ITEM NO	ITEM DESCRIPTION	QTY	UNIT	RATE		AMOUNT (Rs)
				IN FIGURES (Rs)	IN WORDS	
1.001	50.6.3.2 Solid block masonry using pre cast solid blocks (Factory made) of size 40x20x10 cm or nearest available size confirming to IS 2185 part I of 1979 for super structure up to floor two level for 10 cm thick wall in : CM 1:6 (1 cement : 6 coarse sand) including cost of scaffolding complete	0.576	Cum			
1.002	13.1.1. 12 mm cement plaster of mix:1:4 (1 cement : 4 fine sand)	5.76	Sqm			
1.003	4.2.3 Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts,buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor, etc. up to floor five level, excluding the cost of centering, shuttering and finishing:1:2:4 (1 Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	0.027	Cum			
1.004	4.3.3 Centering and shuttering including strutting, propping etc. and removal of form work for:Columns, piers, abutments, pillars, posts and struts	0.72	Sqm			
1.005	15.28.1 Dismantling roofing including ridges, hips, velleys and gutters etc., and stacking the material within 50 metres lead of :G.S. Sheet	54.4	Sqm			



1.006	10.16.1 Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc.	148.944	Kg			
1.007	13.52.1 Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On steel work	21.76	Sqm			
1.008	12.50 Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+0.05%), total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (5.5x55mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required	87.1	Sqm			
1.009	12.4.2 Providing ridges or hips width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.63 mm thick with zinc coating not less than 275 gm/m ²	10.2	Metre			
TOTAL						
					18% GST	
					Grand total	
(Rupees.....Only)						

Signature :

Name & Address of the Tenderer:

Date:



REGISTRAR
 REGISTRAR
 KANNUR UNIVERSITY
 CIVIL STATION. P. O.
 KANNUR - 670 002

