

KANNUR UNIVERSITY
(PLANNING AND DEVELOPMENT BRANCH)

NOTICE INVITING TENDERS

15/09/2026

PLD-E/E-4/15553/2026

Sealed competitive Tenders, superscribed as **Electrical work (AC Installation)** at **MMTTC, Thavakkara campus** are invited from registered competent Contractors/firms.

The Details are as follows.

Sl.No.	Name of Work	EMD	Tender fee	Time for the completion of work	Last date and time of submission
1	2	3	4	5	6
1	Electrical work (AC Installation) at MMTTC, Thavakkara campus , Thavakkara campus	Rs. 3145/-	₹590/- (GST18% included)	90Days	22/09/2026 at 3 PM

1. Tender Form can be downloaded from the Kannur University Website www.kannuruniversity.ac.in.
 2. A sum of ₹590/- (GST 18% included) towards the cost of Tender form and an amount of Rs.3145/- as EMD should be remitted separately by way of Demand Draft drawn in favor of Finance Officer, Kannur University, payable at SBI South Bazar Branch, Kannur or Kannur Branch of any other Nationalized or scheduled Bank.
 3. The Contractor shall ensure that before submitting tender for the work, the Contractor visits the site and satisfies himself about the site conditions for construction and for logistics and smooth flow of workmen and materials as well as permission from the Authorities for this purpose.
 4. The Tenderer shall have a valid GST registration and shall furnish a copy of the registration certificate along with the tender documents.
 5. Assistant Engineer(Electrical), Kannur University shall be the Engineer-in-Charge.
 6. The Defect Liability Period shall be 1 year from the date of completion of work, and the contractor shall be responsible to maintain all his works till completion of the Defect Liability Period and to hand over the work to the Engineer in charge.
 7. The successful Tenderer before signing the Agreement and within the period specified in the work order, shall deposit a sum equivalent to 5% of the value of the contract as Security Deposit.
 8. The rate quoted should be inclusive of GST and all other charges if any. The base rate, GST charges, and other charges, if any, should be furnished separately, and nothing extra shall be admissible over and above the rate quoted.
- Payment will be made through the account, and no advance payment will be sanctioned



10. Received tenders will be opened on 22/09/26 at 3.30 PM.

11. Tender schedule is appended.

The Details of work can be had from the Engineering wing of the University, Thavakkara, Kannur, on all working days up to 5 pm.

The Registrar, Kannur University, reserves the right to reject any of the tenders or all the tenders without assigning any reason whatsoever.

sd-

Registrar



KANNUR UNIVERSITY							
TENDER SCHEDULE FOR ELECTRICAL WORK OF AC INSTALLATION AT MMTTC,THAVAKKARA CAMPUS							
LAST DATE OF SUBMISSION:							
SL. NO	ITEM DESCRIPTION	UNIT	QUANTITY	RATE IN FIGURES	RATE IN WORDS	AMOUNT	REMARKS
1	Supplying and drawing following sizes of FRLS PVC insulated copper conductor,single core cable in the existing surface / recessed steel/ PVC conduit as required.4 x 6 sq. mm	Metre	27				
2	Supplying and drawing following sizes of FRLS PVC insulated copper conductor,single core cable in the existing surface / recessed steel/ PVC conduit as required.1x 2.5 sq. mm	metre	27				
3	Supplying and drawing following sizes of FRLS PVC insulated copper conductor,single core cable in the existing surface / recessed steel/ PVC conduit as required.3 x2.5 sq. mm	metre	270				
4	Supply and fixing following double pole type switch/socket on the existing switch box/cover including connections etc.as required 32 amp switch	each	8				
5	Supplying and fixing following piano type switch/ socket on the existing switch box/cover including connections etc. as required.6 pin 15/16 amp socket outlet	each	8				
6	Supplying and fixing following Modular base& cover plate on existing modular metal boxes etc. as required.1 or 2 Module	each	16				
7	Supply&fixing16A 3 Pin Top	each	8				
8	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface/ recess including cutting the wall and making good the same in case of recessed conduit as required.25 mm	metre	241				
9	Supply & Fixing the following types/ sizes of boxes suitable for modular accessories in surface/ recess including making good the damages, colour washing etc as required (RoHS compliant)2 module moulded plastic box on surface	each	16				
10	Supplying and fixing Cable End Box (Loose Wire Box) (IP 43) suitable for following triple pole and neutral, sheet steel, MCB distribution board, 415V, on surface/ recess,complete with testing and commissioning etc. as required.For 4 way, Double door SPN MCBDB	each	1				
11	Supplying and fixing 40 A rating, 415 volts, 15 kA, ""C"" curve, miniature circuit breaker suitable for inductive load of following Four poles in the existing MCB DBcomplete with connections, testing and commissioning etc. as required.Four pole and netural	each	1				
12	Supplying and fixing 5A to 32 A rating, 240/415 volts, 10 kA, ""C"" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.Single pole	each	6				
TOTAL AMOUNT							
GST 18%							
GRAND TOTAL							
(RupeesOnly)							
SIGNATURE				REGISTRAR			
Name & Address							
Date							

